



2520 Urbana Pike
 ljamsville, MD 21754
 301-428-9040 Fax 301-874-2564
www.longfence.com

Attention: **Estimating**

DUE DATE: 4/4/2025

WE ARE PLEASED TO SUBMIT THE FOLLOWING QUOTE FOR:
Wastewater Treatment Plant Fence

Page 1 of 3

Scope:

Install Approx. 585Lf of 6'+1'H Black Chain Link

Install (1) 4'W x 6'+1'H Single Gate

Install (1) 25'W x 6'+1'H Aluminum Cantilever Slide Gate

***Fence installed with top rail, bottom tension wire and (3) strands of barb wire

*** All posts set through earth in wet cement

*** Aluminum slide gate to be installed with operator - All Access Control and Electrical work by others

***See Page 3 for Operator Materials List

***Pricing does not include grounding

Materials to consist of:

Chain Link Mesh - 2" x 9 Gauge x 72" Black Vinyl Coated Chain Link Mesh

Terminal and Single Gate Posts - 3" OD SS40 Black Vinyl Coated Pipe

Line Posts - 2 1/2" OD SS40 Black Vinyl Coated Pipe

Top Rail, Bracing, and Single Gate Frame - 1 5/8" OD SS40 Black Vinyl Coated Pipe

Aluminum Cantilever Gate Frame - 2" x 2" x .25" Aluminum Tube

Barb Wire - 4 Pt. 12.5 Gauge Class III Vinyl Coated Barb Wire

Bottom Tension Wire - 7 Gauge Coil Spring Tension Wire

Single Gate Hardware - Industrial Offset 180° Hinges; Commercial Gate Fork Latch

Total - \$49,450.00

Following exceptions in addition to standard exclusions on page 2:

* 6' High Temporary Fence in Blocks: \$4.50 Per LF / Plus Tax - Minimum \$500.00

** Please see additional pages for continued scope Yes XXX No

Prices are: XXX Furnished Include Bond
 XXX Installed XXX Exclude Bond

We have seen the following addenda: None

We have seen the following plan sheets: Plan Sheet 16 - Drawings Dated 1/9/2023

We have seen the following spec. sections:

Spec Section 02821 - Pages 1-13

Our quote is valid for a period of 14 days for purpose of acceptance.

If you have any questions regarding our bid or wish to discuss the above information please contact:

TJ Master

at 301-428-9040 ext.

3119

Thank you for the opportunity to quote your firm on this project.



Page 2 of 3

Exclusions -Engineering, Layout, fine grading, seeding, sod replacement, permits, as-builts, liability for damage to private utilities, determination of property lines, engineered stamped drawings, traffic control, grounding, clearing of fence line, control points, materials testing, primary and secondary electrical work, padlocks on gates, any work not specifically described in quote.

Vage Determinations, compliance fees for outside sourcing of payroll or insurance monitoring, fees for training classes, CCIP, OCIP

Damage to any geogrid products due to the installation of our products.

Prevailing Wage, Domestic materials, and LEED are not figured in this quote

Please note that all temporary fence is a leased product. All temporary fence shall remain the property of Long Fence and be kept in good repair by lessee.

Please note: There will be an additional outside fee of \$200 for any outside online monitoring services associated with this order.

Drug Screening requirements or safety classes required for Long Fence Employees will be an additional fee of \$250.00 per employee.

For Bridge Fencing Long Fence will not core drill holes for post plate bolts after a wall is poured if the wall rebar is not adjusted to accommodate core drilling.

If a wall is designed as slip form or precast a separate price may be given if requested and a copy of the rebar placement must be furnished prior to fence submittals.

NOTICE:

Long Fence has been experiencing unmanageable increases in material pricing accompanied by shortages in available inventories far beyond prior market volatility.

Long Fence has been notified that many products currently have significantly extended lead times that may have an impact on availability if orders are delayed.

Material List:

- (1) LiftMaster Model INSL24UL, Industrial Duty Slide Gate Operator with Battery Backup.
- (1) Post Mount for Slide Operators.
- (1) LiftMaster Gate Edge Kit.
- (1) LiftMaster Model LMMRUL Monitored Photo Eye.
- (2) Sawcut Vehicle Loops in Asphalt for Free Exit and Reversing.
- (1) Labor to Install.

Exclusions: All Electrical Work Including All Necessary Conduits, Primary, Secondary and Control Wiring. All Access Control, Pedestals and Concrete Foundations for them. Any Emergency Vehicle Device.